



AS BUILT CHECKLIST

Project: _____ **Date:** _____

Town of Williston
7900 Williston Road
Williston, VT 05495
•
1763
•
Public Works
(802) 878-1239

Sanitary Sewers:

Accurate location & depths of all sanitary sewer lines, manholes & appurtenances	
Accurate measurements & depths to all services for building connections	
Location & depths of building connections at property lines	
Invert & manhole rim elevations, distances between manholes, size, type and slope of pipes	
Location and depths of all cleanouts	
Results of leakage tests on pipelines and manholes	
Location and width of any sewer easements	

Water Distribution

Accurate locations of all water line, valves & appurtenances	
Accurate measurements and depths to all valves, tees, bends, curb stops and any other fittings from permanent fixtures such as telephone poles, hydrants, buildings, transformers, etc.	
All curb boxes shall be marked with stakes so contractors can easily locate them before building services are connected.	
Results of hydrostatic, leakage and disinfection tests on all pipelines	
Location and width of any water easements	

Stormwater Facilities

Depth, size, location and type of all storm drain line and culverts, including underdrains and services along with elevations	
Location, size of all catch basins	
Rim and invert elevations of all catch basins	
Location and details for all storm drainage facilities such as detention ponds	
Location of all drainage ways, water courses, etc.	
Location and width of drainage easements	

Highways

Accurate location of all streets	
Width of pavement from curb to curb or shoulder to shoulder	
Right-of-way dimensions for streets	
Width of sidewalks and bike paths	
Location of street lights	
Location of driveways	
Location and size of planter islands	
Typical cross-section of streets as installed with date of completed construction	
Location of all underground electric, gas, telephone lines and crossing sleeves	
Radius of all corners	
Results of all sieve analysis and compaction tests	