

Chamberlin Lane Water Line Upgrade

The replacement of the existing waterline on Chamberlin Lane has been identified for future upgrade. In Taft Farms, an existing 8” waterline is looped on Isham Circle. Beginning at the intersection of Isham Circle, the existing 8” waterline extends north on Chamberlin Lane about 620’, then transitions to a 12” waterline. With the new water storage tank located on Mountainview Road, this is a critical north/south link for the High Service area, so upgrade of this existing 8” waterline with a new 12” waterline is planned.

So as to limit the need for additional easements, use of temporary water service is planned so that the new 12” waterline can be laid in next to the existing 8” waterline. This project will have temporary disruptions on both Isham Circle and Chamberlin Lane during this activity. There are 9 homes along Chamberlin Lane, see plan sheet attached, that will be affected the most with this project and will require a temporary water line to be installed for the duration of the project. The project is to take place this construction season, but a firm date has not been determined. The actual length of construction should be 45 days.

There will be an informational meeting held on April 4, 2024 in the Town Hall Meeting Room located at 7900 Williston Road at 7:00 PM to explain the project. This meeting will be either in person or via ZOOM at link below:

<https://us02web.zoom.us/j/81052274275?pwd=S0EyN0JxNTlsaVdnRDdRFZk96ZHI1QT09>

Meeting ID: 810 5227 4275

Passcode: 940584

Please direct any questions to Bruce K. Hoar, Public Works Director by email at bhoar@willistonvt.org or phone at (802) 878-1239

